
#### Proposal for FCAL-II Upgrade



A 32x32 matrix of PWO insert (~64x64 cm<sup>2</sup> in size, a total of 1024 PWO detector modules) with a 2x2 matrix (~4x4 cm<sup>2</sup>) beam hole to replace 247 channels of the Pb glass modules in the central region of the existing FCAL

# Unit Price of a PWO Detector

Item	Cost per channel
PWO Crystal (2.05cmx2.05cmx18cm)	\$820
PMT	\$310
HV divider	\$50
PMT housing	\$50
Flash ADC	\$340
HV	\$310
HV cable	\$100
Signal cable	\$50
Total	\$2030

### **Estimated total cost**

#### (Calorimeter with 32 x 32 modules = 1020 channels)

Item	Channels	Unit Cost	Cost	
PWO crystal	1050	\$820	\$0.86M	
PMT+base+house	1050	\$410	\$0.43M	
Flash ADC	660 (reuse FCAL/CCAL)	\$340	\$0.22M	
HV	910 (reuse CCAL)	\$310	\$0.28M	
HV cables	910 (reuse CCAL)	\$100	\$0.09M	
Signal cables	910 (reuse CCAL)	\$50	\$0.05M	
Frame	1	\$150 k	\$0.15M	
Chiller & control equipment	1	\$50 k	\$0.05M	
VXS crate+electronics	3	\$34.5 k	\$0.1M	
Light monitoring	1	\$30 k	\$0.03M	
Total			\$2.26M	
Contingency(20%)			\$0.47M	
Total+Contingency			\$2.71M	

## FCAL II fabrication and Installation

Assemble 1050 CCAL modules: 6 months, 2 people (time estimates are based on the CCAL fabrication experience)

**FCAL restacking:** 

Unstack FCAL modules	-	2	months
Install new frame	-	2	months
Stack CCAL/FCAL modules	-	2.5	months
Attach PMTs/cables install LMS	-	1.5	months

Total time: 8 months

Note, some installation proceedures can be done in parallel